### Con Edison Dielectric Fluid Spill Prevention, Detection & Response Best Practices



Environment, Health and Safety

### Joint RRT 1 & 2 Meeting

Vernon Schaefer, Brian DeShong April 12, 2017



# Agenda


- Transmission System Overview
- Leak Detection
- Leak Causes
- Leak Search Process
- Pipe Enhancement as a Preventative Measure
- Spill Response and Cleanup





# **Transmission Feeder Systems**

- High Pressure Fluid Filled Feeders
  - 660 circuit miles
  - 8.7 million gallons dielectric fluid
- Dielectric Fluid
  - Dielectric fluid impregnated paper insulation is one of the best insulating mediums
  - Utilize cooling to increase rating







# Leak Detection

- Detection Programs
  - Online leak detection systems on 22 feeders
  - Refurbishment of pressurization plants with early warning leak detection
  - Daily tank level monitoring & trending





# **Dielectric Fluid Leak Committee**

To establish and provide guidelines for a standing committee for detecting and locating leaks on dielectric fluid filled cable systems. The Dielectric Fluid Leak Committee will ensure that leaks are rapidly detected, located, and repaired to minimize the impact on the environment.





# Leak Causes

- Contractor damage
- Water impingement
- Coating separation (disbonded coating)
- Corrosion due to stray current





### 345kV Feeders M51 & M52 NYCTA Drain Bond Installation





# M51 & M52 2015 Leaks

- Factory pipe coating is coal tar wrap (CTW)
- Each feeder contains approximately 390,000 gallons
- Protected with impressed current rectifiers
- 2015 leaks: 11,645 gallons to environment (42%)
- Harlem River Drive section: 8,586 gallons (74%)






# **Cathodic Protection**

- Electric Transmission pipe type feeders use impressed current rectifiers
- Optimal pipe to soil potential is -0.85 volts or less (more negative)
- Feeders M51 & M52 installed in 1974
  - Initial stray currents as a result of NYCTA along Broadway
  - Electrical interference from DC traction system affects cathodic protection
  - Drain bonds installed at NYCTA Substations:
    - LOCATIONS REDACTED CRITICAL INFRASTRUCTURE INFORMATION
- Stray current effects mitigated in this area in 1980's






### **Stray Current Problem**





### **Drain Bond Installation**






# 2015 Stray Currents

- Since January 2015, 19 leaks have occurred on the Harlem River Drive north of W155<sup>th</sup> Street
- Not a known historic leak area only three leaks prior to January, 2015 spread over several pipe sections
- Cathodic protection testing
  - Initial tests by Con Edison
  - Further testing in collaboration with NYCTA
- Testing revealed a stray current concern with Feeders M51 & M52 in the same area of increased number of leaks
- Drain bond installed to NYCTA'sREDACTED Substation
  - completed on June 14, 2016






### **Pipe Potential Testing**








### **Pipe Potential Testing**





### **Drain Bond Currents**







# **PFT Leak Search**






### **PFT Leak Search** HIGH-PRESSURE FLUID FILLED FEEDERS

#### **PIPE-TYPE FEEDERS**


High-Pressure Fluid-Filled



#### ISSUE AT HAND

Dielectric Fluid Leaks

Locating leaks can be difficult
Adding a highly evaporative chemical tracer -Perfluorocarbon Tracer (PFT) to the dielectric fluid can help us locate the leak





### **PFT Leak Search** FEEDER LEAK SEARCH PROGRAM


#### PATROL PROCEDURE

Identify General Leak Area

**TERMINAL SUBSTATION 1** 



**TERMINAL SUBSTATION 2** 






### **Barhole Analysis** FEEDER LEAK SEARCH PROGRAM

#### **BARHOLE PROCEDURE**

Pinpoint Specific Leak Area






# Excavation

#### FEEDER LEAK SEARCH PROGRAM


#### **BARHOLE PROCEDURE**

Pinpoint Specific Leak Area






# **PFT Detection Challenges**





# **PFT Detection Challenges**

- Duct work / piping
- Subway
- Plating
- Residual from old leak





### **PFT Detection Challenges**







# **Pipe Enhancement Program**





# **Pipe Enhancement Program**

- Feeders M51, M52 are the worst performers in terms of leaks
- Areas to be addressed are selected based on study of historic leak locations, pipe-to-soil potentials, and keyhole inspections
- Selected areas are excavated, stripped of coating (ACM), inspected, permanently repaired (welded sleeves), new coating applied, and street fully restored






# **Initiatives to Reduce Leaks**

- Increase pipe refurbishment to account for new section of leak-prone pipe along Harlem River Drive
  - Adding 1,500 additional trench feet of pipe refurbishment each year over next two years (2017, 2018)
  - Incremental annual cost = \$8.5 million per year
  - Address stray current along Harlem River Drive to prevent re-occurrence
  - Total pipe refurbished in 2017 and 2018 up to 7,500 trench feet
- Replace labor-intensive coal tar removal / taping method with Teflon/carbon fiber wrap epoxy method
  - Little asbestos abatement required





# Accelerated Refurbishment of Leak-Prone Pipe (2016 - 2018)





### **Pipe Enhancement Process**

- Close Interval Survey / Keyhole
   Inspections
- Community Impact / Outreach
- Impact from other Utilities





## **Disbonded/Damaged Coating**











### **Coating Removal and Inspection**







### **Typical Corrosion Damage**











### **Interference** Issues





### **Pipe Repairs and New Coating**





### **Pipe Repairs and New Coating**





# Spill Response & Cleanup





# **Spill Management Team**

- Corporate team created to respond to and manage significant spills to waterways
  - Quarterly meetings/training sessions
  - Members from EH&S and Operations
  - Coordination with US Coast Guard and NYSDEC
- Responses
  - Hutchinson River 3<sup>rd</sup> party damage to feeder



- Bronx River Y50 Feeder in Yonkers 4 miles to Bronx Zoo
- B3402/C3403 Marina Spill ongoing in Jersey City





# Oil Spill Contingency Plans and Offsite Oil Spill Response Plans

- Identifies and prioritizes critical water use/sensitive areas for expedient spill containment, cleanup and recovery
  - Oil Spill Contingency Plans 300+ Substations and Steam Stations
  - Offsite Oil Spill Response Plans 15 feeders in Westchester County
- Plans contain off-site drainage pathways and preidentified spill response deployment areas/actions
  - Response maps are field-verified on a periodic basis






Consolidated Edison Company of New York, Inc. Transmission Operations Fluid Filled Feeder Y50

### Table 2-1

#### SPILL RESPONSE DEPLOYMENT ACTIONS Bronx River Drainage Basin

Location Figure(s) Scenario Action Place drain covers and Identify catch basins and protect storm drain inlets; Oil is contained outfalls in the vicinity of the 1 - 1deploy containment to and/or has not source of the oil. outfall vet reached the Identify all outfalls storm sewer Deploy containment to connected to storm pipes 1-1 system outfall discharging from nearby catch basins. Identify all outfalls Deploy containment to connected to storm pipes 1 - 1discharging from nearby outfall catch basins. Oil has entered Place drain covers and the storm sewer Identify catch basins and protect storm drain inlets: system but has outfalls in the vicinity of the 1-1 deploy containment to not yet reached a source of the oil. outfall waterbody Identify spill response Deploy containment to deployment area protect downstream 2 - 1immediately downstream of sensitive areas outfall. Deploy containment at Hunts Point (DEP Boom) furthest downstream 2-3 location of oil impacts Deploy containment at Westchester Avenue Bridge 2-3 downstream location Railroad trestle north of Deploy containment at 2-3 downstream location Westchester Avenue Bridge Oil has reached a Deploy containment to Jungle World Road Bridge 2-3 waterbody protect sensitive areas (i.e., Boston Post Road) Upstream of Bronx Zoo Deploy containment to (East Fordham Road/Pelham 2-2/2-3 protect sensitive areas Parkway) Mosholu Parkway and Allerton Avenue exit off Deploy containment at 2-2 Bronx River Parkway downstream location underpass

+3263/NN10181602\_Y49







**Offsite Oil Spill Response Plan Response Maps** redacted due to confidentiality and sensitivity of utility infrastructure location information






















# **Contain, Divert and Collect**











# **Crucial Skimmers – Clean Harbors Co-op**




Skimmer in Newport Marina in Jersey City, NJ

## Skimmer on Bronx River in Yonkers, NY



































































## **Operation Overview Map**

## Note: Scale only for Fixed Structures



# **Communication with Stakeholders**

- Open communication with stakeholders is key
- Develop relationships on "blue sky" days for successful incident response outcomes
  - Familiarization tours
  - "Con Ed 101" training
  - NY/NJ Area Committee
  - Quarterly Task Force meetings









# **Questions?**



